Sequencer 3 - Triple Duty Standby/Assist Relay

DIN rail mounted electronic relay to alternate startups between 3 pumps

• For DIN Rail Mounting

- Ideal for OEM integration and panel building
- Alternately Chooses Between 3 Connected Pumps (Pump Alternation) When an Input Switch is Closed
- Duty Assist Input Activates Both Outputs Simultaneously
- Can be Used with Pressure or Level Based Controls

Current status of connected pumps in system

Status of pump protection for each connected pump

Buttons allowing manual activation or deactivation of connected pumps

Sequencer 3 displays system status with LEDs and manual control buttons.

Please note that **Sequencer 3** is not supplied with a pressure switch or float switch. Please call to discuss the available options when ordering.

How Does It Work?

Mac3 **Sequencer 3** is a DIN rail mounted load sequencing relay which can be used to evenly distribute run time between 3 pumps in duty standby/assist configuration . This is useful if a installation has multiple pumps, and the installer requires all pumps to have the same level of use.

Sequencer 3 starts the pumps in rotation, which prevents the same pump being run each time the system is activated. This also allows the controller to activate additional pumps when a single pump cannot meet requirements.

The system is activated by a primary pressure switch, which establishes demand on the system and two additional pressure switches which each activate separate pumps.

Dry run protection is provided through the use of a float switch, which prevents pumps from being activated if a insufficient level of water is detected.

Technical Specifications

Physical	
Material - Body	Noryl (PPO) UL94 V0
Weight	420g
Dimensions	105x90v73 mm
Mounting	DIN Rail (EN50022)
Ingress Protection	IP20
Electrical	
Supply Voltage	110/230Vac 50-60Hz Single Phase
Pressure Switch Voltage	2Vac
Float Switch Voltage	24Vac
Power Consumption	8VA max
Life Expectancy	
Mechanical	2 Million Operations
Electrical	100,000 Operations With A Normal Load
Number Of Operations	10 Operations/Minute Max.
Contact Rating	250 V~ 5A max AC 1250 VA inductive Cos φ = 1 AC 500 VA inductive Cos φ = 0,4 DC 150 W resistive
Operating Temperature	-30°C – +80°C




01239 623506

<u>www.mac3uk.com</u>

Sequencer 3 - Triple Duty Standby/Assist Relay

DIN rail mounted electronic relay to alternate startups between 3 pumps



3P Technik UK Limited Unit 9 Parc Teifi Cardigan SA43 1EW

Phone : 01239 62350

sales@3ptechnik.co.uk

www.3ptechnik.co.uk www.mac3uk.com

